Drawing Analysis Results

AI Analysis Summary

Plan View: R2.0 (page 2)

Scale: AS NOTED

roof_drains: 4 | mechanical_units: 3 | sleeper_curbs: 3 | vent_hoods: 2 | gas_penetrations: 1

Detail refs: 1/R3.2, 5/R3.0, 2/R3.2, 5/R3.1, 1/R3.1, 4/R3.1, 4/R3.0

Details: R2.1 (page 3)

> **SECTION #3 - ROOF SLOPE PLAN** [field_assembly] - measured in: sqft
>
> - 1. TAPER PACKAGE AT 2% SLOPE → Polyisocyanurate_ISO_Insulation (2.4m wide around perimeter of roof; leaves 300mm wide channels)

Details: (page 4)

> **ROOF DRAIN** [drain] - measured in: each
>
> - 1. EXISTING STRUCTURAL CONCRETE → None
> - 2. FILL VOID WITH MINERAL WOOL INSULATION → Batt_Insulation
> - 3. SET DRAIN INTO PERIMETER SEALANT → Sealant_General
> - 4. INSTALL NEW DRAIN INSERT INTO EXISTING PIPE → Roof_Drain (SUPPLY INSERT WITH 150mm FLANGE)
> - 5. SECURE MEMBRANE WITH CLAMPING RING → Roof_Drain
> - 6. APPLY FLEECE REINFORCED ALSAN RS MEMBRANE AROUND ROOF DRAIN → Fleece_Reinforcement_Fabric (MINIMUM DIMENSION OF 1500x1500mm (59 inches))
> - 7. PROVIDE NEW GRAVEL GUARD AROUND DRAIN → Gravel_Ballast
> - 8. DRAIN DOME → Roof_Drain

> **GAS LINE PENETRATION** [penetration_gas] - measured in: each
>
> - 1. PROVIDE FIRESTOP SEALANT BETWEEN PIPE AND SHEET METAL → Sealant_General
> - 2. TWO PIECE FLAT STOCK 26GA STEEL CUT ON SITE TIGHT TO PIPE PENETRATION → Coated_Metal_Sheet (FASTEN TO DECK WITH EIGHT 25mm ZAMAC PIN BOLTS EQUALLY SPACED. LAP MEMBRANE ONTO METAL MINIMUM 150mm(6").)
> - 3. CONTINUE MEMBRANE BELOW NEW CURB → Base_Membrane
> - 4. INSULATE WITH MINERAL WOOL INSULATION → Batt_Insulation

- 5. PROVIDE NEW DIMENSIONAL LUMBER AND PLYWOOD CURB AROUND PENETRATION → Wood_Blocking_Lumber (FILL ENTIRE CAVITY WITH MINERAL WOOL INSULATION. COVER STUDS WITH 13mm PLYWOOD SHEATHING AROUND PERIMETER AND TOP)
- 6. NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (FINISH TIGHT TO INSULATION BELOW BALLAST)
- 7. PROVIDE SELF-ADHERED BASE SHEET AROUND CURB → Base_Membrane (DO NOT TORCH TO WOOD SHEATHING.)
- 8. PROVIDE FLEECE REINFORCED LIQUID APPLIED FLASHING AROUND PENETRATION → Liquid_Membrane_Flashing
- 9. PROVIDE 22GA PREFINISHED STEEL COVER FLASHING OVER FULL CURB → Coated_Metal_Sheet (ONE PIECE METAL SLEEVE. NO SHARP EDGES. COVER MUST BE REMOVABLE. FASTEN WITH FOUR HEX HEAD #8 WOOD SCREWS)
- 10. PROVIDE NEW SHUT-OFF VALVE IN ADDED PIPE SECTION → None
- 11. REPAINT GAS LINES TO MATCH EXISTING → Coating_Paint

ROOF ASSEMBLY [field_assembly] - measured in: sqft

- 1. STRUCTURAL CONCRETE DECK → None
- 2. EXISTING ROOF MEMBRANE → None
- 3. NEW ROOF BASE SHEET → Base_Membrane
- 4. ROOF CAP SHEET → Cap_Membrane
- 5. 10mm DRAINAGE MAT → Drainage_Board (10mm)
- 6. 75mm EXTRUDED POLYSTYRENE INSULATION (XPS) → XPS_Insulation (75mm)
- 7. FILTER FABRIC → Filter_Fabric
- 8. REMOVE AND REPLACE GRAVEL BALLAST TO MAXIMUM 100mm → Gravel_Ballast (100mm)

PARAPET / CURB DETAIL [parapet] - measured in: linear_ft

- 1. INSTALL FOAM BACKER ROD BELOW AIR/VAPOUR BARRIER → Sealant_General
- 2. NEW VAPOUR BARRIER AT TRANSITION FROM CONCRETE DECK TO WALL → Vapour_Barrier_Membrane
- 3. 26GA GALVANIZED STEEL METAL IN L SHAPE → Coated_Metal_Sheet (FASTEN INTO PRE-CAST AT 300mm WITH 6.4mm DIAMETER PIN BOLTS)
- 4. BASE AND CAP SHEET MEMBRANE TRANSITION FROM TOP OF CURB TO WALL → SBS_2Ply_Modified_Bitumen (LEAVE LOOSE LOOP. LAY MEMBRANE HORIZONTALLY TO MINIMIZE JOINTS)
- 5. TERMINATE MEMBRANE AT UPTURN WITH NEW 25mm CONT. CLAMPING BAR → Clips (FASTEN WITH 38mm HEX HEAD SCREWS AT 400mm O/C.)
- 6. PRECAST PANEL TO REMAIN IN PLACE → None

EXPANSION JOINT / PARAPET [expansion_joint] - measured in: linear_ft

- 1. PROVIDE NEW DIMENSIONAL LUMBER TO ACCOMMODATE NEW INSULATION → Wood_Blocking_Lumber
- 2. PROVIDE NEW 25MM WIDE POLYISOCYANURATE INSULATION → Polyisocyanurate_ISO_Insulation (25MM WIDE)
- 3. 12mm GYPSUM SHEATHING → DensDeck_Coverboard (MECHANICALLY FASTENED INTO STRUCTURE OF CURB. USE 50mm SELF TAPPING CORROSION RESISTANT #8 FLAT HEAD OR PAN HEAD SCREWS WITH 50mm PLATES C/W

NEOPRENE GASKET)

- 4. PROVIDE NEW 18 ga STEEL STUD FRAMING C/W TOP AND BOTTOM TRACKS → None (ANCHOR TO DECK WITH SMACK PINS, 38mm LENGTH WITH MINIMUM 6mm EMBEDMENT INTO CONCRETE, INSTALL AT 300mm O/C IN STAGGERED W PATTERN FASTEN STUDS TO TRACKS WITH #10 SELF-TAPPING PAN HEAD SCREWS)
- 5. NEW 13mm PLYWOOD SHEATHING → Plywood_Sheathing (SCREW AT TOP AND BOTTOM AT 300mm O/C)
- 6. NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (FINISH TIGHT TO INSULATION BELOW BALLAST)
- 7. INFILL JOINT WITH MINERAL WOOL → Batt_Insulation
- 8. BASE AND CAP SHEET AT EXPANSION JOINT → SBS_2Ply_Modified_Bitumen (LEAVE A LOOP IN BASE AND CAP SHEET AT EXPANSION JOINT)
- 9. REMOVE AND REINSTATE METAL CAP FLASHING → Flashing_General
- 10. PROVIDE 24GA PRE-FINISHED STEEL FLASHING TO COVER TERMINATION BAR → Coated_Metal_Sheet (FASTEN AT BASE WITH 6.4mmø PIN BOLTS EMBEDDED 38mm SPACED AT MAX. 400mm O/C. FIT TOP INTO EXISTING REGLET AND FINISH WITH SEALANT)

Details: 5 (page 5)

Small Opening Cover [opening_cover] - measured in: each

- 1. TAPCON PHILLIPS HEAD, 44mm (1-3/4") LENGTH → Screws (4 per countersunk plate)
- 2. 3mm STEEL PLATE COVER → Coated_Metal_Sheet (Covering the opening)

Large Opening Cover [opening_cover] - measured in: each

- 1. 38x38x6.4 ANGLE FULLY AROUND PERIMETER → Flashing_General (Perimeter support)
- 2. 38x38x6.4 STEEL ANGLE ON EDGE → Flashing_General (Space at 450 O/C max. in single direction)
- 3. TAPCON PHILLIPS HEAD 38mm → Screws (Min. 8 per opening)
- 4. 3mm STEEL PLATE COVER → Coated_Metal_Sheet (Top cover plate)

Mechanical Support Curb [sleeper_curb] - measured in: linear_ft

- 1. #8 CONCRETE SCREWS AT 150mm O/C → Screws (Fasten to existing slab)
- 2. NEW WOOD BLOCKING AS REQUIRED → Wood_Blocking_Lumber (Base structure)
- 3. NEW 13mm PLYWOOD SHEATHING → Plywood_Sheathing (Curb sheathing)
- 4. NEW 24GA PREFINISHED STEEL COUNTER FLASHING → Flashing_General (Finish tight to insulation below ballast)
- 5. 24ga GALVANIZED STEEL STRAPPING → Flashing_General (4 straps in total, from leg onto side of curb)
- 6. NEW 22GA PRE-FINISHED STEEL CAP FLASHING → Flashing_General (Cap over curb)
- 7. 50mm HEX HEAD #14 FASTENERS WITH RUBBERIZED GASKET → Fasteners (Face fastened)
- 8. SEALANT BEAD → Sealant_General (Perimeter heel bead at footing)

Typical Mechanical Curb [mechanical_curb] - measured in: linear_ft

- 1. NEW DIMENSIONAL LUMBER AS REQUIRED → Wood_Blocking_Lumber (To provide 200mm upturn)

- 2. 6mm ASPHALTIC CORE BOARD OR 12mm GYPSUM SHEATHING → Gypsum_Fiber_Coverboard (Mechanically fastened into structure of curb)
- 3. 50mm SELF TAPPING #8 FLAT HEAD OR PAN HEAD SCREWS WITH 50mm PLATES → Screws (C/w neoprene gasket)
- 4. BASE MEMBRANE → Base_Membrane (Return base membrane over curb and fasten with ring nails)
- 5. NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (Finish tight to insulation below ballast)

Mechanical Unit Transition Detail [mechanical_curb] - measured in: linear_ft

- 1. FLEECE REINFORCED PMMA MEMBRANE → Fleece_Reinforcement_Fabric (Apply at existing seams and from flashing to steel channel)
- 2. NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (Finish tight to insulation below ballast)
- 3. HEX HEAD 50mm CONCRETE SCREWS C/W GASKET → Screws (Fasten @ 300mm O/C)

Mechanical Unit Transition Detail Type [mechanical_curb] - measured in: linear_ft

- 1. NEW BASE AND CAP SHEET → Base_Membrane (Installed up under the existing mechanical unit frame)
- 2. NEW 24GA PRE-FINISHED STEEL FLASHING → Flashing_General (Finish tight to insulation below ballast)
- 3. HEX HEAD 50mm CONCRETE SCREWS C/W GASKET → Screws (Fasten @ 300mm O/C)
- 4. SEALANT BEAD → Sealant_General (Apply at leading edge)
- 5. FLEECE REINFORCED PMMA MEMBRANE → Fleece_Reinforcement_Fabric (Apply at existing seams and from flashing to steel channel)

Details: 5 (page 6)

ROOF TO CURTAIN WALL DETAIL [curtain_wall] - measured in: linear_ft

- 1. NEW 12.5mm PLYWOOD ON EXTERIOR → Plywood_Sheathing (12.5mm thickness (~0.5 inch))
- 2. MINERAL WOOL INSULATION → Batt_Insulation (Fill gaps)
- 3. NEW SOPREMA 1100HT SELF-ADHERED MEMBRANE CURTAIN WALL SHOULDER → Vapour_Barrier_Membrane (Self-adhered membrane for shoulder transition)
- 4. NEW 26GA METAL BREAKSHAPE TO TRANSITION → Flashing_General (Transition from curb to curtain wall framing)
- 5. NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (Finish tight to insulation below ballast)
- 6. NEW DRIP FLASHING AT CURTAIN WALL → Drip_Edge (Capture by pressure plate and anti-rotation block)

TYPICAL PARAPET DETAIL [parapet] - measured in: linear_ft

- 1. NEW DIMENSIONAL LUMBER AND WOOD BLOCKING → Wood_Blocking_Lumber (To build up parapet, fasten into concrete parapet with hex head #8 concrete screws)
- 2. NEW 12.5mm PLYWOOD SHEATHING → Plywood_Sheathing (On interior face of parapet wall. Fasten with 50mm pin bolts.)

- 3. 24GA PRE-FINISHED STEEL COUNTER FLASHING → Flashing_General (Max 2.4m lengths. Utilize S-locks on vertical joints.)
- 4. CONTINUOUS 22GA GALV. STEEL CLIP → Clips (On exterior face. Fasten at 400mm O/C.)
- 5. 24GA PREFINISHED STEEL CAP FLASHING → Flashing_General (Face fasten interior at 400mm O/C. Slope 5% min. Standing seam at corners and S-lock in cap flashing.)

Specification PDF Analysis (Deterministic Regex Engine)

24 unique products found across **7** categories — **11** mapped to pricing keys.
Project: 2026 Roof Replacement

- ▶ **Membranes (8)**
- ▶ **Sealants & Adhesives (4)**
- ▶ **Drainage (4)**
- ▶ **Miscellaneous (3)**
- ▶ **Fasteners & Hardware (1)**
- ▶ **Insulation (1)**
- ▶ **Metal Flashings & Accessories (3)**

Spec-Driven Pricing Estimate (Drawing spatial data + Specification materials — deterministic)

LINE ITEMS RESOLVED	RESOLUTION FAILURES	TOTAL MATERIAL COST
11	**3**	**$578.78**

Resolved Line Items

DETAIL	TYPE	CONFIRMED MATERIAL	QTY	UNIT PRICE	LINE COST	SOURCE
SECTION #3 - ROOF SLOPE	field_assembly	2-Ply SBS Membrane System	1 roll	$298.00	$298.00	FAL
				Total Material Cost	**$578.78**	

DETAIL	TYPE	CONFIRMED MATERIAL	QTY	UNIT PRICE	LINE COST	SOURCE
PLAN R2.1		`SBS_Membrane` spec pg 30, 49				
ROOF DRAIN	drain	Gravel Ballast `Gravel_Ballast` spec pg 48	1 sqft	$0.75	$0.75	FAL
GAS LINE PENETRATION	penetration_gas	Sealant (General) `Sealant_General` spec pg 2, 11, 14, 30, 48, 57, 64, 68, 69, 70, 71, 72	1 tube	$29.86	$29.86	FAL
ROOF ASSEMBLY	field_assembly	Gravel Ballast `Gravel_Ballast` spec pg 48	1 sqft	$0.75	$0.75	FAL
PARAPET / CURB DETAIL	parapet	Sealant (General) `Sealant_General` spec pg 2, 11, 14, 30, 48, 57, 64, 68, 69, 70, 71, 72	1 tube	$29.86	$29.86	FAL
Small Opening Cover 5	opening_cover	Wood Screws `Screws` spec pg 46	1 box	$39.96	$39.96	FAL
Large Opening Cover 5	opening_cover	Wood Screws `Screws` spec pg 46	1 box	$39.96	$39.96	FAL
Mechanical Support Curb 5	sleeper_curb	Sealant (General) `Sealant_General` spec pg 2, 11, 14, 30, 48, 57, 64, 68, 69, 70, 71, 72	1 tube	$29.86	$29.86	FAL
				Total Material Cost	**$578.78**	

DETAIL	TYPE	CONFIRMED MATERIAL	QTY	UNIT PRICE	LINE COST	SOURCE
Typical Mechanical Curb 5	mechanical_curb	Wood Screws `Screws` spec pg 46	1 box	$39.96	$39.96	FAL
Mechanical Unit Transition Detail 5	mechanical_curb	Wood Screws `Screws` spec pg 46	1 box	$39.96	$39.96	FAL
Mechanical Unit Transition Detail Type 5	mechanical_curb	Sealant (General) `Sealant_General` spec pg 2, 11, 14, 30, 48, 57, 64, 68, 69, 70, 71, 72	1 tube	$29.86	$29.86	FAL
				Total Material Cost	**$578.78**	

⚠ Material Resolution Failures (3)

These drawing details could not be matched to a confirmed material in the Specification PDF. Either the spec PDF does not cover these items, or additional regex patterns are needed in `database.PRODUCT_KEYWORDS`.

- **EXPANSION JOINT / PARAPET** expansion_joint (ref:)

  Expected one of: `Coated_Metal_Sheet`, `SBS_2Ply_Modified_Bitumen`, `Batt_Insulation`, `Plywood_Sheathing`, `DensDeck_Coverboard`, `Polyisocyanurate_ISO_Insulation`, `Wood_Blocking_Lumber`, `Flashing_General`, `EPDM_Accessory`, `TPO_Accessory` — none confirmed in spec.

- **ROOF TO CURTAIN WALL DETAIL** curtain_wall (ref: 5)

  Expected one of: `Drip_Edge`, `Vapour_Barrier_Membrane`, `Batt_Insulation`, `Plywood_Sheathing`, `Flashing_General`, `Metal_Flashing_Galvanized`, `Metal_Flashing_Prepainted` — none confirmed in spec.

- **TYPICAL PARAPET DETAIL** parapet (ref: 5)

  Expected one of: `Clips`, `Plywood_Sheathing`, `Wood_Blocking_Lumber`, `Flashing_General`, `Metal_Flashing_Galvanized`, `Metal_Flashing_Prepainted`, `Cap_Membrane`, `Base_Membrane` — none confirmed in spec.

Detail-Based Quantity Takeoff (AI-Analyzed)

ROOF AREA	PERIMETER	PARAPET	PENETRATIONS
13,580 sqft	**625 LF**	**625 LF x 0.0 ft**	**9**

SECTION #3 - ROOF SLOPE PLAN [field_assembly] (ref: R2.1)

Measured in: sqft | Base value: 13,580.4 | Detail cost: $40,741.08 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
TAPER PACKAGE AT 2% SLOPE	934 sheet (4'x4')	$43.62	$40,741.08

ROOF DRAIN [drain] (ref:)

Measured in: each | Base value: 4 | Detail cost: $1,567.60 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
EXISTING STRUCTURAL CONCRETE	5 unit	$0.00	-
FILL VOID WITH MINERAL WOOL INSULATION	1 bundle	$83.99	$83.99
SET DRAIN INTO PERIMETER SEALANT	1 tube	$29.86	$29.86
INSTALL NEW DRAIN INSERT INTO EXISTING PIPE	4 EA	$325.00	$1,300.00
SECURE MEMBRANE WITH CLAMPING RING	0 EA	$0.00	-
APPLY FLEECE REINFORCED ALSAN RS MEMBRANE AROUND ROOF DRAIN	1 roll	$150.00	$150.00
PROVIDE NEW GRAVEL GUARD AROUND DRAIN	5 sqft	$0.75	$3.75
DRAIN DOME	0 EA	$0.00	-

GAS LINE PENETRATION [penetration_gas] (ref:)

Measured in: each | Base value: 1.0 | Detail cost: $1,890.12 qty: unit_perimeter G

Unit Breakdown:

- G-1: 1.57 LF perimeter (Near raised roof section)

MATERIAL	QTY	UNIT PRICE	LINE COST
PROVIDE FIRESTOP SEALANT BETWEEN PIPE AND SHEET METAL	0 tube	$0.00	-
TWO PIECE FLAT STOCK 26GA STEEL CUT ON SITE TIGHT TO PIPE PENETRATION	1 sheet (4'x10')	$583.11	$583.11
CONTINUE MEMBRANE BELOW NEW CURB	1 roll	$127.25	$127.25
INSULATE WITH MINERAL WOOL INSULATION	0 bundle	$0.00	-
PROVIDE NEW DIMENSIONAL LUMBER AND PLYWOOD CURB AROUND PENETRATION	1 8ft piece	$16.59	$16.59
NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING	1 10ft piece	$75.00	$75.00
PROVIDE SELF-ADHERED BASE SHEET AROUND CURB	0 roll	$0.00	-
PROVIDE FLEECE REINFORCED LIQUID APPLIED FLASHING AROUND PENETRATION	2 unit	$0.00	-
PROVIDE 22GA PREFINISHED STEEL COVER FLASHING OVER FULL CURB	0 sheet (4'x10')	$0.00	-
PROVIDE NEW SHUT-OFF VALVE IN ADDED PIPE SECTION	0 unit	$0.00	-
REPAINT GAS LINES TO MATCH EXISTING	1 pail	$1,088.17	$1,088.17

ROOF ASSEMBLY [field_assembly] (ref:)

Measured in: sqft | Base value: 13,580.4 | Detail cost: $91,177.05 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
STRUCTURAL CONCRETE DECK	0 unit	$0.00	-
EXISTING ROOF MEMBRANE	0 unit	$0.00	-
NEW ROOF BASE SHEET	0 roll	$0.00	-
ROOF CAP SHEET	174 roll	$150.00	$26,100.00
10mm DRAINAGE MAT	50 roll (6'x50')	$410.53	$20,526.50
75mm EXTRUDED POLYSTYRENE INSULATION (XPS)	934 sheet (2'x8')	$43.70	$40,815.80
FILTER FABRIC	14939 sqft	$0.25	$3,734.75
REMOVE AND REPLACE GRAVEL BALLAST TO MAXIMUM 100mm	0 sqft	$0.00	-

PARAPET / CURB DETAIL [parapet] (ref:)

Measured in: linear_ft | Base value: 625.3 | Detail cost: $0.00 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
INSTALL FOAM BACKER ROD BELOW AIR/VAPOUR BARRIER	0 tube	$0.00	-
NEW VAPOUR BARRIER AT TRANSITION FROM CONCRETE DECK TO WALL	0 roll	$173.66	-
26GA GALVANIZED STEEL METAL IN L SHAPE	0 sheet (4'x10')	$0.00	-
BASE AND CAP SHEET MEMBRANE TRANSITION FROM TOP OF CURB TO WALL	0 unit	$7.00	-
TERMINATE MEMBRANE AT UPTURN WITH NEW 25mm CONT. CLAMPING BAR	0 piece	$10.19	-

MATERIAL	QTY	UNIT PRICE	LINE COST
PRECAST PANEL TO REMAIN IN PLACE	0 unit	$0.00	-

EXPANSION JOINT / PARAPET [expansion_joint] (ref:)

Measured in: linear_ft | Base value: 156.3 | Detail cost: $493.56 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
PROVIDE NEW DIMENSIONAL LUMBER TO ACCOMMODATE NEW INSULATION	0 8ft piece	$0.00	-
PROVIDE NEW 25MM WIDE POLYISOCYANURATE INSULATION	0 sheet (4'x4')	$0.00	-
12mm GYPSUM SHEATHING	6 sheet (4'x8')	$33.52	$201.12
PROVIDE NEW 18 ga STEEL STUD FRAMING C/W TOP AND BOTTOM TRACKS	0 unit	$0.00	-
NEW 13mm PLYWOOD SHEATHING	6 4'x8' sheet	$48.74	$292.44
NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-
INFILL JOINT WITH MINERAL WOOL	0 bundle	$0.00	-
BASE AND CAP SHEET AT EXPANSION JOINT	0 unit	$0.00	-
REMOVE AND REINSTATE METAL CAP FLASHING	0 10ft piece	$0.00	-
PROVIDE 24GA PRE-FINISHED STEEL FLASHING TO COVER TERMINATION BAR	0 sheet (4'x10')	$0.00	-

Small Opening Cover [opening_cover] (ref: 5)

Measured in: each | Base value: 3 | Detail cost: $39.96 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
TAPCON PHILLIPS HEAD, 44mm (1-3/4") LENGTH	1 box	$39.96	$39.96
3mm STEEL PLATE COVER	0 sheet (4'x10')	$0.00	-

Large Opening Cover [opening_cover] (ref: 5)

Measured in: each | Base value: 3 | Detail cost: $0.00 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
38x38x6.4 ANGLE FULLY AROUND PERIMETER	0 10ft piece	$0.00	-
38x38x6.4 STEEL ANGLE ON EDGE	0 10ft piece	$0.00	-
TAPCON PHILLIPS HEAD 38mm	0 box	$0.00	-
3mm STEEL PLATE COVER	0 sheet (4'x10')	$0.00	-

Mechanical Support Curb [sleeper_curb] (ref: 5)

Measured in: each | Base value: 3 | Detail cost: $350.00 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
#8 CONCRETE SCREWS AT 150mm O/C	0 box	$0.00	-
NEW WOOD BLOCKING AS REQUIRED	0 8ft piece	$0.00	-
NEW 13mm PLYWOOD SHEATHING	0 4'x8' sheet	$0.00	-
NEW 24GA PREFINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-
24ga GALVANIZED STEEL STRAPPING	0 10ft piece	$0.00	-
NEW 22GA PRE-FINISHED STEEL CAP FLASHING	0 10ft piece	$0.00	-

MATERIAL	QTY	UNIT PRICE	LINE COST
50mm HEX HEAD #14 FASTENERS WITH RUBBERIZED GASKET	1 box (1M)	$350.00	$350.00
SEALANT BEAD	0 tube	$0.00	-

Typical Mechanical Curb [mechanical_curb] (ref: 5)

Measured in: linear_ft | Base value: 16.0 | Detail cost: $0.00 qty: unit_perimeter V

Unit Breakdown:

- V-1: 8.0 LF perimeter (Near RTU #2)
- V-2: 8.0 LF perimeter (Near RTU #1)

MATERIAL	QTY	UNIT PRICE	LINE COST
NEW DIMENSIONAL LUMBER AS REQUIRED	0 8ft piece	$0.00	-
6mm ASPHALTIC CORE BOARD OR 12mm GYPSUM SHEATHING	0 sheet (4'x8')	$29.62	-
50mm SELF TAPPING #8 FLAT HEAD OR PAN HEAD SCREWS WITH 50mm PLATES	0 box	$0.00	-
BASE MEMBRANE	0 roll	$0.00	-
NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-

Mechanical Unit Transition Detail [mechanical_curb] (ref: 5)

Measured in: linear_ft | Base value: 16.0 | Detail cost: $0.00 qty: unit_perimeter RTU #2

Unit Breakdown:

- RTU2: 16.0 LF perimeter (West)

MATERIAL	QTY	UNIT PRICE	LINE COST
FLEECE REINFORCED PMMA MEMBRANE	0 roll	$0.00	-
NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-
HEX HEAD 50mm CONCRETE SCREWS C/W GASKET	0 box	$0.00	-

Mechanical Unit Transition Detail Type [mechanical_curb] (ref: 5)

Measured in: linear_ft | Base value: 20.0 | Detail cost: $0.00 qty: unit_perimeter RTU #1

Unit Breakdown:

- RTU1: 20.0 LF perimeter (Center)

MATERIAL	QTY	UNIT PRICE	LINE COST
NEW BASE AND CAP SHEET	0 roll	$0.00	-
NEW 24GA PRE-FINISHED STEEL FLASHING	0 10ft piece	$0.00	-
HEX HEAD 50mm CONCRETE SCREWS C/W GASKET	0 box	$0.00	-
SEALANT BEAD	0 tube	$0.00	-
FLEECE REINFORCED PMMA MEMBRANE	0 roll	$0.00	-

ROOF TO CURTAIN WALL DETAIL [curtain_wall] (ref: 5)

Measured in: linear_ft | Base value: 625.3 | Detail cost: $472.65 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
NEW 12.5mm PLYWOOD ON EXTERIOR	0 4'x8' sheet	$0.00	-
MINERAL WOOL INSULATION	0 bundle	$0.00	-

MATERIAL	QTY	UNIT PRICE	LINE COST
NEW SOPREMA 1100HT SELF-ADHERED MEMBRANE CURTAIN WALL SHOULDER	0 roll	$0.00	-
NEW 26GA METAL BREAKSHAPE TO TRANSITION	0 10ft piece	$0.00	-
NEW 24GA PRE-FINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-
NEW DRIP FLASHING AT CURTAIN WALL	69 10ft piece	$6.85	$472.65

TYPICAL PARAPET DETAIL [parapet] (ref: 5)

Measured in: linear_ft | Base value: 625.3 | Detail cost: $0.00 qty: fallback

MATERIAL	QTY	UNIT PRICE	LINE COST
NEW DIMENSIONAL LUMBER AND WOOD BLOCKING	0 8ft piece	$0.00	-
NEW 12.5mm PLYWOOD SHEATHING	0 4'x8' sheet	$0.00	-
24GA PRE-FINISHED STEEL COUNTER FLASHING	0 10ft piece	$0.00	-
CONTINUOUS 22GA GALV. STEEL CLIP	0 piece	$0.00	-
24GA PREFINISHED STEEL CAP FLASHING	0 10ft piece	$0.00	-

Total Material Cost **$136,732.02**

Standard Estimate (for comparison)

Standard Total Estimate	**$378,555.79**